

TENDER

For

Making Cots with Head Board and 2 Side Storage (60 Sets) & Re-Painting of rooms in Participant Rooms in 5th, 6th & 7th Floor of EFC Building in IDRBT Premises, Masabtank, Hyderabad – 500 057

Part – II (Commercial/Price Bid)

Name of the Tenderer: _____

Address: _____

Due date and time for submission of tender:

17.00 hours on 18.01.2016

Signature of the Tenderer

INSTITUTE FOR DEVELOPMENT AND RESEARCH IN BANKING TECHNOLOGY

No.	Description of Item	U O M	Qty.	Rate	Rate in Words	Amount
1	<p>Supply, Making and Fixing of Wooden Cot/ Bed of Size (L)6'3" X (B)3' X (H)1'3" made of best quality BT Teak wood. The wood must be properly treated for termite proofing. Side plank of Section (H) 6" X (W) 1.5" , Legs of Section 2.5" X 2.5". The Base of the bed to be 12 mm Water Proof & Termite Proof plywood (Greenply) with 3 Nos. BT Teak Wood supports of section (H) 2" X (W) 1.5" placed neatly 1" from the top of side plank of the Bed/Cot. All BT Wood surfaces to be polished with approved shade. The rate for the work must include the supply of all materials, labour, Clamps, Bolts & other necessary fixtures including all applicable taxes, transportation, wastage etc. A sample is available at the premises (R.No. 515, EFC Building) for reference.</p>	E a c h	60	₹		₹

Signature of the Tenderer

2	<p>Supply, Making and Fixing of Head board of size (L)6' X (H)4' with 12 mm Water Proof and Termite Proof Plywood (Greenply) with frame made of 18 mm ply of 2" width at the back of the board. The head board is to be provided with 1 mm thick decolam sheet of approved colour in the form of (H) 6" X (W) 6' pieces of alternate colours and a gap of 3 mm between each piece of decolam. The Decolam pieces to be fixed from the top of bed till the top of the head board. The rate for the work must include the supply of all materials, labour, Clamps, Screws, Gum & other necessary fixtures & Hardware including all applicable taxes, transportation, wastage etc. A sample is available at the premises (R.No. 515, EFC Building) for reference.</p>	E a c h	60	₹		₹
---	---	------------------	----	---	--	---

3	<p>Supply, Making and Fixing of Side box of size (L) 1'6" X (B) 1' X (H) 1' 8" made of 12 mm Water Proof & Termite Proof Plywood (Greenply). The Box should have 1 shelf inside. The Outer Periphery of the box including the Shutter shall be laminated with Decolam Sheet of 1 mm thickness of approved colour and White Decolam sheet of 0.8 mm thickness from the inside. The box should have a shutter and all appropriate fixtures like a good quality lock, SS hinges(2 Inch) and SS Handle etc. to be included. The rate for the work must include the supply of all materials, labour, Clamps, Screws, Gum & other necessary fixtures & Hardware including all applicable taxes, transportation, wastage etc. A sample is available at the premises (R.No. 515, EFC Building) for reference.</p>	E a c h	104	₹		₹
---	--	------------------	-----	---	--	---

Signature of the Tenderer

4	<p>Hand Finish Polishing of existing polished wooden surfaces with approved shade of polish as directed. The rate for the work must include the supply of all materials, labour, Hardware, including all applicable taxes, transportation, wastage etc.</p>	S q. Ft .	936	₹		₹
5	<p>Supply and Fixing of 1 mm thick decolam sheet of approved make and shade, as directed, over existing Ply Wood Surfaces after removal of polishing or old laminates. The rate for the work must include the supply of all materials, labour, Gum & other necessary fixtures & Hardware including all applicable taxes, transportation, wastage etc.</p>	S q. Ft .	416	₹		₹

<p>6 Supply and Fixing of 4 mm thick mirror glass of size (H) 5' X (W) 1'6" with 6 MM Plywood backing properly fixed onto the wall with all necessary fixtures. The Rate should also include a glass shelf below the mirror of size 18" X 6" . The rate for the work must include the supply of all materials, labour, Clamps, Screws, Gum & other necessary fixtures & Hardware including all applicable taxes, transportation, wastage etc.</p>	<p>E a c h</p>	<p>52</p>	<p>₹</p>		<p>₹</p>
<p>7 Supply and application of 1 coat of Wall Putty of approved brand and 2 Coats of Plastic Emulsion paint of Approved brand and Shade as desired after removal and cleaning of existing painting wherever required or asked for. The rate for the work must include the supply of all materials, labour, Paint Brushes & other necessary Hardware including all applicable taxes, transportation, wastage etc.</p>	<p>S q. Ft .</p>	<p>27200</p>	<p>₹</p>		<p>₹</p>

Total Amount of the Work:	₹
Additional Discounts(If Any) in %:	
Total discount applicable:	₹
Gross Amount of work after applying all discounts:	₹

Total Amount in Words: Rupees _____

Place:
Date:

Signature of the firm
with seal and date