

**PRICE BID FOR CENTRE FOR CYBER SECURITY (ANNEX-2)**

No.	Description of Item	UOM	Qty.	Rate in Words (In Rs.)	Rate in Figures (In Rs.)	Amount (In Rs.)
1	Providing and Fixing of GI covered trench of width 250 MM & Depth of 25-40 MM beneath the floor level by properly aligning and fixing the trenches in their place with bolts or screws. The rates must also include providing and fixing of Stainless Steel (wire brush finish) cover plates on the flooring of minimum size of 250 * 250 MM with 4 nos 10 MM holes for wire entry. the plate shall be fixed to the floor with minimum 4 nos. of screws at the corners. Total Plates required are 25.	MTRS.	40.00			
2	Providing and Fixing of GI covered trench of width 100 MM & Depth of 25-40 MM beneath the floor level by properly aligning and fixing the trenches in their place with bolts or screws. The rates must also include providing and fixing of Stainless Steel (wire brush finish) cover plates on the flooring of minimum size of 100 * 100 MM with 1 no 10 MM hole for wire entry. The plate shall be fixed to the floor with minimum 4 nos. of screws at the corners. Total Plates required are 20.	MTRS.	40.00			
3	Providing and fixing of 600 MM X 600 MM size tiles of approved shade and design from a reputed manufacturer in flooring and skirting wherever required and as directed by the EIC. Any work related to matching of levels for flooring shall be in the contractor's scope and no extra payment shall be made. The rates must include cost of all consumables, labour, tools and tackles, transportation and applicable taxes. BASIC RATE OF TILE SHALL BE UPTO RS. 750 (+/- 10%) PER SQ. MTR.	SQ.M.	120.00			
4	Painting of walls and ceiling wherever required with application of 1 coat of putty and 2 coats of distemper of the approved colour. The rates must include the cost of labour, tools & tackles, cost of paint, paint brushes, Putty, Minor civil touchup work, transport machines and all items required for satisfactory completion of the work & all applicable taxes if any.	SQ.M.	250.00			
5	Brickwork in cement mortar 1:5 and plastering on both sides of total thickness of 250 MM (10 Inches)	CU.M	10.00			

**PRICE BID FOR CENTRE FOR CYBER SECURITY (ANNEX-2)**

No.	Description of Item	UOM	Qty.	Rate in Words (In Rs.)	Rate in Figures (In Rs.)	Amount (In Rs.)
6	2' X 2' Mineral Fiber Board ceiling(Armstrong make) same as that already available in the room with birds mouth runner channels(armstrong)	SQ.M.	20.00			
7	Providing and fixing of Flush door in double door format including teak wood frame. Includes 2 nos dorma door closers, towerbolt, aldrip & Glass window of size 300 x 450. the entire dore should be 4 feet wide and 7 feet in height	LS	1.00			
8	Repairs to the existing furnitre of the CCS lab. The work includes fixing of new clamps at all joints and refurbishing the desks to usable condition. One desk has to be modified to provide storage space. All as per site conditions.	LS	1.00			
9	Removal of Aluminium doors/partitions, Steel shutters, Shelf at the back and carting away from site.	LS	1.00			
10	Buyback of item no. 9 above	LS	-1.00			
<b>SUB TOTAL OF ALL ITEMS:</b>						
<b>GOODS AND SERVICES TAX @ ____% ON ABOVE:</b>						
<b>GRAND TOTAL OF ALL WORKS:</b>						

Amount in Words: **Rs.** \_\_\_\_\_