

ANNEXURE-2, SUPPLY AND INSTALLATION OF CUBICLES, WORKSTATIONS, STORAGE UNITS ETC. AT 2ND FLOOR, EFC BLOCK -PRICE BID

No.	Description of Item	UOM	Qty.	Rate(In Rs.)	Amount(In Rs.)
1	<p>Providing and fixing of Wooden Shutters with necessary framework of hardwood/sandwiched plywood, hinges, door magnets, and other hardware etc.with 18 MM (IS 710 BWP Grade) thick Plywood Laminated with 1 MM thick decorative laminates on exterior face and 0.8 MM plain laminate on the interior face of approved shade.</p> <p>MODE OF MEASUREMENT: Length & Height of the front face shall be measured for calculating the area.</p>	SQ.M.	15.00		
2	<p>Providing and fixing of Wooden Cubicles/ workstations having a work station height of 0.75 Mtr and partition of 75/100 mm thickness of height 1.2 Mtr throughout the length of the cubicle with necessary framework of hardwood/sandwiched plywood, other hardware etc.with 18 MM (IS 710 BWP Grade) thick Plywood Laminated with 1 MM thick decorative laminates on exterior face and 0.8 MM plain laminate on the interior face of approved shade. the front side of the workstation must be thickened (36 mm) with sandwiched plywood of 50 mm width. A Storage unit with one drawer fixed with telescopic channels and one openable cabinet of height & depth equivalent to table top and width of 0.45 mtr for every partitioned workstation to be provided. 12 MM Toughened glass partition (Plain/frosted) to be provided as per instructions of Engineer in-Charge. Pinboard to be provided on all wooden surfces above table top height till top of partition. Vertical Posts with cavity in middle for running cables from ceiling to workstations is to be made of plywood as per instructions of engineer in-charge A keyboard tray of 0.5 Mtr length and 0.25 Mtr Depth rested on telescopic channels to be provided in each partitioned work station. Cable Manager for drawing wires to be provided. providing and fixing 25/40/50 mm PVC Conduits with necessary bends and junctions in concealed manner inside the wooden partitions for drawing of cables from ceiling to each work station.</p> <p>MODE OF MEASUREMENT: Length & width of the table top surface of the work station/cubicle shall be measured for calculating the area.</p>	SQ.M.	18.00		

ANNEXURE-2, SUPPLY AND INSTALLATION OF CUBICLES, WORKSTATIONS, STORAGE UNITS ETC. AT 2ND FLOOR, EFC BLOCK -PRICE BID

No.	Description of Item	UOM	Qty.	Rate(In Rs.)	Amount(In Rs.)
3	<p>Providing and fixing of Wooden Cubicles/workstations/tables having a work station height of 0.75 Mtr with necessary framework of hardwood/sandwiched plywood, other hardware etc.with 18 MM (IS 710 BWP Grade) thick Plywood Laminated with 1 MM thick decorative laminates on exterior face and 0.8 MM plain laminate on the interior face of approved shade. the front side of the workstation must be thickened (36 mm) with sandwiched plywood of 50 mm width. A Storage unit with one drawer and one openable cabinet of height & depth equivalent to table top and width of 0.45 mtr for every workstation to be provided. Pinboard to be provided on all walls adjacent to the table/ cubicle with necessary plywood/cardboard frame as per instructions of Engineer in charge</p> <p>MODE OF MEASUREMENT: Length & width of the table top surface of the work station/cubicle shall be measured for calculating the area.</p>	SQ.M.	12.00		
4	<p>Providing and fixing of Wooden Storage units with shutters & necessary internal partitions as instructed by Engineer-in-Charge of various sizes as per requirement., Including necessary framework other hardware etc.with 18 MM (IS 710 BWP Grade) thick Plywood Laminated with 1 MM thick decorative laminates on exterior face and 0.8 MM plain laminate on the interior face of approved shade. Height and width may vary to any extend as per the requirement and space available, however, depth shall be in the range of 0.65 Mtr to 0.45 Mtr. The item shall be completed as per instructions of Engineer in charge. A keyboard tray of 0.5 Mtr length and 0.25 Mtr Depth rested on telescopic channels to be provided in each Table/Work Station.</p> <p>MODE OF MEASUREMENT: Width and Height of the Front face of the Storage unit shall be measured for calculating the area.</p>	SQ.M.	20.50		

ANNEXURE-2, SUPPLY AND INSTALLATION OF CUBICLES, WORKSTATIONS, STORAGE UNITS ETC. AT 2ND FLOOR, EFC BLOCK -PRICE BID

No.	Description of Item	UOM	Qty.	Rate(In Rs.)	Amount(In Rs.)
5	Providing and Fixing of Conference table of height 0.75 Mtr. And various length and breadth with necessary vertical supports at required intervals. Hollow box like structure under the table to be provided for running of electrical wires as per instructions of the Engineer-in-charge. The front side of table top should be made of sandwiched (36 mm) plywood of 50 mm width as per instructions of engineer incharge. Item inclusive of all required hardware. All surfaces to be laminated with 1.0 MM thick laminate of approved shade. MODE OF MEASUREMENT: Length & width of the table top surface of the Conference Table shall be measured for calculating the area.	SQ.M.	7.00		
TOTAL BASE TENDER VALUE:					
GST @ ___% ON TOTAL BASE TENDER VALUE:					
TOTAL TENDER VALUE:					
Amount In Words:					

IMPORTANT NOTES FOR FILLING IN THE QUOTE

1	The Actual quantity may vary for item no. 4 above as per requirement. However, the minimum quantity of work shall be 4 Sq. Metre				
2	Attached drawings in Annexure-3 must be referred for quoting for the items				
3	Any item that has some deficiency in the description written above but the work cannot be satisfactorily completed without such component, the components shall be deemed included in the rate quoted by the vendor.				
4	APPROVED BRANDS/MAKES OF ITEMS TO BE USED:				
(a)	Plywood (BWP Grade)	Century/Greenply Conforming to IS:710			
(b)	1.0/0.8 MM Thick Decorative/Plain Laminate	Greenlam/Century/Virgo			
(c)	Hardware fittings (Hinges, magnets, locks, handles, Telescopic Channel etc.	Hafele/Hettich/Dorset/Godrej			
(d)	Glass 12 MM Toughened (Plain/Frosted)	Saint Gobain			